

Maximising modular design within healthcare | Brunel University 2021Andy King – DirectorE: Andy.king@wernick.co.uk | TEL: 01656 747340 | DDI: 01656 747351 | EXT: 5122 | MOB: 07817 561341



The Wernick Group


- Established in 1934, the UK's oldest modular builder
- ► Family run company with 750 employees
- £150m+ annual turnover
- Nationwide coverage with 32 Depots throughout the UK
- Factories in South Wales and York producing over 1500sqm of modular buildings per week



BUILDINGS

Overall benefits of modular in healthcare

- A simple design process using proven designs & systems
- ► A simple procurement process using national frameworks
- Shorter programmes and reduced disruption on site through off site working
- Minimised construction waste through efficient factory processes
- Sustainable, easily reconfigurable, relocatable and easily recyclable
- Greater value for money through process, design and overall programme efficiencies








Delivering Modular benefits

- Early Engagement
- Procurement processes
- Standardised Design
- Manufacturing efficiencies
- Factory & Site programme
- Overall benefits of Modular






Early engagement - the key to modular success



Andy King – Director



Early engagement - the key to modular success



Procurement process

Multiple national frameworks are available






Modular manufacturing processes, not bespoke build






Four bed room typical width is circa 7.6m






- ► Four bed room
- Standard modules are typically 3.0m wide





- Four bed room
- New standard 3.8m modules have be created







Queen Alexandra Hospital























Major verses minor changes







George Elliot Operating Theatre

- 800m2 twin laminar flow operating theatre with recovery space
- > 20 week programme from design order to completion
- Full height 3m canopy with 1.5m service space delivered via use of floorless modules




Maximising modular design within healthcare | Brunel University 2021 Andy King – Director



Sustainable and reconfigurable

 Structurally open plan modules up to 12m allow for future reconfiguration and relocation





Minimise construction waste

Breeam Excellent target 19kg/m²

Module manufacture: 262 kg = 0.262 kg/m²

Factory module fit out: $4,071 \text{ kg} = 4.071 \text{ kg/m}^2$

Site fit out: 11,080 kg = 11.08 kg/m²

Total waste generated = 15.151 kg/m²

Percentage of waste recycled and diverted from landfill = <u>98%</u>





Programme and site operations


 Lighter weight buildings allow for simpler foundations





Programme and site operations

- Efficient module & layout design allow more factory fit out to be achieved
- Larger modules require fewer deliveries





Programme and site operations

 Offsite manufacture and fit out mean less disruption to the busy hospital site





Overall benefits of modular in healthcare

- A simple design process using proven designs & systems
- A simple procurement process using national frameworks
- Shorter programmes and reduced disruption on site through off site working
- Minimised construction waste through efficient factory processes
- Sustainable, easily reconfigurable, relocatable and easily recyclable
- Greater value for money through process, design and overall programme efficiencies







Any questions?





